Enabling Efficient Electrification to help decarbonise the railway

Colin Lamb (Scotland Region)

Richard Stainton (STE)

Climate Change Context

NetworkRail

UK Climate Change Act 2008 passed into law binding UK to reducing emissions by 80% from 1990 levels by 2050.



Climate Change Act 2008



In July 2019 the Decarbonisation Taskforce publishes its final report.

Scottish Government aim to decarbonise railway by 2035

December 2015 Paris Agreement established seeking to limit global average temperature increase to well be below 2°C and to pursue efforts to limit this to 1.5°C

In June 2019 the UK Government revised the 2008 Climate Change Act to commit to a target of net-zero greenhouse gas emissions by 2050. In Feb 2018, then minister for rail Jo Johnson MP challenges the industry to remove all diesel-only trains from the network by 2040

May 2019 CCC recommends

to the UK government that a

revised UK target of Net-zero

emissions by 2050 should be

established

In response to the minister the rail industry convened the Decarbonisation Taskforce to explore decarbonisation in rail



Ш

In January 2019 the Decarbonisation Taskforce publishes its interim report noting that it is possible to remove diesel only passenger trains but this is harder for freight

Climate Emergency declared by

Climate Emergency declared by Scotland Government, Wales Assembly and UK Government.

Traction Emissions kgCO₂e / kWhr

0.83

0.62

0.6

0.63

0.7

8.0

0.5

0.33

0.4

0.16



Source RSSB T1145 - Options for Traction Energy Decarbonisation in Rail ³

Diesel Hybrid Diesel Advanced Hybrid Diesel **OLE Electrification 2018 OLE Electrification 2040** Natural Gas (CNC / LNG) LPG Brown Hydrogen (Natural Gas) Brown Hydrogen (Electrolysis 2018) Brown Hydrogen (Electrolysis 2040) Green Hydrogen

Biodiesel

THE SUNDAY TIMES

CLEAN AIR FOR ALL Call to cut diesel trains over air pollution risk



Ultra low

emission

ULEZ

ZONE

At all times

Graeme Paton, Transport Correspondent

July I 2019, 5:00pm, The Times

Transport



Scientists found a link between the number of diesel trains in and the concentration of nitrogen dioxide ALAMY

Source RSSB T1122 – Research into air quality in enclosed stations



So how do we make electrification efficient?

Scotland electrification challenge and opportunities

- Continue electrification in CP6 onwards, following successful CP5 projects
- TS requirement in High Level Output Specification for CP6 efficient electrification specification
- 3 September 2019 the First Minister in her Programme for Government (PfG) gave a commitment to decarbonise domestic railway services in Scotland by 2035

NetworkRail

- Phase 1 electrification projects launched CP6/CP7 delivery
- Task Group setup to outline a prioritised rolling programme, items to be considered are the interdependent workstreams:



NetworkRail





Scotland Fleet Deployment and Future Options

14

Ref	Current Fleet Deployment	Future Considerations
1 2	 Currently running Class 156/8s on rural lines These will be life expired by the mid-2020's 	 Scenic trains are likely to drive the next DMU procurements The West Highland and Kyle lines are the drivers but all rural routes are likely to take the same stock
3		 Capacity is also a key consideration on the West Highland, G&SW and Stranraer lines
4		
5	 Intercity HSTs will run until 2030 on Inverness to Glasgow and Edinburgh 	For the future of these services journey times will be the most important consideration between Inverness and Aberdeen/Edinburgh/Glasgow
6	 Aberdeen to Glasgow and Edinburgh 	 However both journey time and capacity will be key between Aberdeen and Edinburgh/Glasgow
7	Currently running Class 158s on local services in the north-east	
8	 These will be life expired by the mid-2020's 	
9		
10	Class 170s will be life expired by 2030	
11		
12	Class 385s are committed to Scotland until 2035-40	
13	The 20m DMU fleet (Class 318/20s) will be life expired by the mid 2020s	Additional capacity will be required on the North Electrics and Argyle Lines

Class 380's currently run on the Ayrshire lines Growth can be managed by fleet cascade of 385s or a new fleet

Electrification Lessons Learnt (1)

Netw	orkRail

Item	EGIP	SDA & Shotts
Contracting Strategy	Alliance between NR & suppliers, model not fully applied and unsuccessful.	Simpler strategy was implemented with multiple principle contractors – improved focus on their specialism.
Development stage of the programme	Key deliverables at early development stage need to be delivered. This would reduce risk and lead to improved quality, cost and programme certainty.	Key deliverables at early development stage need to be delivered. This would reduce risk and lead to improved quality, cost and programme certainty.
Clearance Works	Pre 2015, track lower and / or reconstruction at 60 overline structures then impacted by new standards, with further implications.	Risk assessments at certain locations where significant clearance challenge to demonstrate risk was ALARP.
Railway (Interoperability) regulations	Ongoing discussion with ORR, resulting in additional works.	Early Engagement with ORR at route and national level. NR Standards updated.
Electrical Station clearances per GLRT1210	Project team developed a risk model.	
Track Access	ROTR access was insufficient for construction works.	Shotts was re-planned to allow greater use of EROTR.
Access Locations	Sufficient road rail access points (RRAPs) essential to maximise construction periods.	
Construction Quality	Initial Alliance focus was on volumes, quality was impacted. Resulting in project entry into service with significant number of snags.	Improved focus on build quality. New NR Standards.

Electrification Lessons Learnt (2)

Item	EGIP	SDA & Shotts
Pile Refusals	Quality of ground investigations led to significant number of refusals. This impacted OLE construction and rework on OLE design.	 Impact on construction quality of build, rework, RaCE - 21% EGIP - 11% SDA - 2% Shotts - 4% New NR Standard issued NR/L2/CIV/074
Lineside Power Supplies		Utilisation of existing signalling power supplies to power OLE switches. This avoided the need for new LV supplies.
Overhead Utilities diversions due to clearances to new OLE		Essential that this is planned at early stage. This leads to cost avoidance.
Construction time impacted due to existing lineside power cables		Consideration of renewals of cables in advance of civils works. Reduced the need for trial holes at each mast location. Potential access time of up to 2 hours due to power up / down requirements.
Use of temporary sidings to maximise access		Redundant sidings brought back into use to improve access for road rail vehicles.

NetworkRail

Benchmark - Swiss OLE Renewal

Frauenfeld – Weinfelden 9 days instead of 600 nights 3 years of planning 13m CHF \approx £10m 34 stk NetworkRail

https://vimeo.com/236053661

726 FUNDAMENTE 623 MASTEN

Acres 44.4

*Jchönholze

100









13





Civils Works

- Tunnels
- Stations
- Bridges

Other

- Signalling
- Fencing
- De-vegetation
- Mobilisation
- TOC Compensation





Civils Works

- Tunnels
- Stations
- Bridges

Other

- Signalling
- Fencing
- De-vegetation
- Mobilisation
- Operator Compensation

Electrification

- Foundations
- Masts
- Wiring
- Commissioning
- Traction Power



Ħ

NetworkRail

Typical	UK Programme

Advanced Works

Track Layout
Ground & Structure Investigation
Traction Power
Signalling & Telecoms

Utilities Diversion

Route Clearance & Civils

- Access Points Structure Reconstruction **Stations Modifications**
- Mast Foundations

Overhead Line & Electrification

Finalise Design & BoQ Install OLE Masts & Registrations

- **Install Wire Runs**
- Panning
- Energise
- **Testing & Commissioning**





NetworkRail

NetworkRail **Opportunities – Rolling Programme Advanced Works** Track Layout Ground & Structure Investigation С Α **Traction Power** Signalling & Telecoms В D **Utilities Diversion Route Clearance & Civils** Access Points С Α Structure Reconstruction Stations Mast Foundations В D **Overhead Line & Electrification** Finalise Design & BoQ С A Install OLE Masts & Registrations **Install Wire Runs** Panning В D Energise Testing & Commissioning

Electrification Commissioned in Scotland



Commissioned [stk]

OLE

Opportunities – Rolling Programme

Commissioned [stk]

OLE



NetworkRail

Opportunities – Managing Risk





Opportunities – Managing Risk

Utilities Ground Conditions Traction Power Signalling & Telecoms Structure Survey

-1-6.

NetworkRail

Electrical clearances



NetworkRail

Ħ

Ħ









Impulse protection level: U10kA - 8/20µs = 75 kV



PTFE Contact Wire Cover (Kago)





Polyurea Coating (GLS100R)





Thickness of Coating	Pass voltage	Fail Voltage
3mm	22kV	25kV
5mm	30kV	35kV
8mm	35kV	38kV

Electrical Stress Graded Bridge Arm

2

Insulated Bridge Arm & Wire Cover



the second second

And the second second

0

and the particular of

2.

17



Insulated Bridge Arm Results



									Clea	rance							
	Mitigation	70 ı	mm	60 ו	mm	50 ı	mm	40 ı	mm	30 r	nm	20 ו	nm	10 r	nm	0 n	าฑ
	Witigation	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-
	Contact Wire Only	***	***														
5	Surge Arrestor	~ ~ ~	~~ ~	~ ~ ~	~~ ~	~ ~ ~	~~	~ ~ ~	~~ ~	~~ ~	√ √ √	~~ ~	×√√				
ā	Surge Arrester and contact wire cover									~~ ~	~ ~ ~	~ ~ ~	× × ×				
	Surge Arrester, contact wire cover and insulated coating											~ ~ ~	~ ~ ~	~~ ~	~ ~ ~	~ ~ ~	√ √ √
	Contact Wire Only																
et	Surge Arrestor			√ √ √	~ ~ ~	***	√ √ √	***	~ ~ ~	* * *	***						
≥	Surge Arrester and contact wire cover					$\checkmark \checkmark \checkmark$	~ ~ ~	~ ~ ~	~ ~ ~	x x x	√xx						
	Surge Arrester, contact wire cover and insulated coating							~ ~ ~	~ ~ ~	~ ~ ~	$\checkmark \checkmark \checkmark$	~ ~ ~	~ ~ ~	√ x x	√ × √	x x x	* * *

Key* = FlashoverFailed with both impulsePassed with one impulsePassed with both* = Passpolaritiespolarityimpulse polarities



Bridge Arm Uplift Measurements Low Speed (<100 kmph)



NetworkRail





Hazard Analysis



NetworkRail

Clearance Compromised OCL - Train Roof

W6a plate in environmental chamber

Clearance Compromised OCL - Train Roof

W6a flashover without surge arrestor



W6a flashover - with surge arrestor

Clearance Compromised OCL - Train Roof

100mm aerial flashover – without surge arrestor

Clearance Compromised OCL - Train Roof

100 mm aerial flashover – with surge arrestor



Contact Wire to Train Roof - with surge arrestor



								Clea	rance							
Test with Surge Arreston	70 ı	nm	60	mm	50 ı	mm	40	nm	30 ו	mm	20 r	nm	10 r	nm	0 n	nm
Test with Surge Arrester	+	-	+	-	+	-	+	-	+	-	+	-	+	-	+	-

Dry	Shaped plate for W6a			~ ~ ~		√ √ x	√ √ √	***	√××		xxx			
	Shaped plate for W10			~ ~ ~		√ √ x	√ √ √	***	×	***	***			
	Shaped plate for W12			~~ ~	~ ~ ~	~~ ~	~ ~ ~	~~	√ √ x	***	xxx			
	Shaped plate with simulated aerial		~ ~ ~	√ √ √	***	√ √ x	× × ×	×√√		***				

	Shaped plate for W6a					~ ~ ~	~ ~ ~	~ ~ ~	√ x √	× × ×	***			
et	Shaped plate for W10			~ ~ ~	√ √ √	~ ~ ~	~ ~ ~	~ ~ ~	√ √ x	***	***			
Ň	Shaped plate for W12			~ ~ ~	~ ~ ~	~ ~ ~	~ ~ ~	~ ~ ~	× × ×	***				
	Shaped plate with simulated aerial		~ ~ ~		√ √ x	√ √ √	√ x √	×√√	***	***	***			

Кеу

× = Flashover √ = Pass Failed with both impulse polarities

Passed with one impulse polarity

Passed with both impulse polarities

Clearance Compromised Pan – Pan Well

Pantograph Horn Testing without surge arrestor

Clearance Compromised Pan – Pan Well

> Pantograph Horn Testing with surge arrestor

Clearance Compromised Pan – Pan Well

Pantograph Horn to Train Roof with surge arrestor

										Clea	rance								
	Test with Surge Arrestor	80 ו	nm	70 r	nm	60 r	nm	50 ו	mm	40 ו	nm	30	mm	20	mm	10 ו	mm	0 n	nm
	Test with Suige Allester		I	+	-	+	-	÷	-	+	-	+	-	+	-	+	-	+	-
	Brecknell Willis HS-A Pan. Horn	√ √ √	√ √ √	~ ~ ~		~ ~ ~	√ √ √	× × ×	~ ~ ~	× × ×	~ ~ ~		× × ×						
2	Brecknell Willis HS-P Pan. Horn (Mk2)	~ ~ ~		×√×		x x x		x x x	~ ~ ~		~ ~ ~		x x x						
D	Brecknell Willis HS-P Pan. Horn (Mk2) Low Stress									√ √ √	~ ~ ~	~ ~ ~	~ ~ ~	x	x				
	Falverley CX Insulated Pan. Horn																	~ ~ ~	~~
	Brecknell Willis HS-A Pan. Horn					~ ~ ~		~ ~ ~	~ ~ ~	×√×	~ ~ ~	× × ×	× × ×						
et	Brecknell Willis HS-P Pan. Horn (Mk2)	~ ~ ~		√ √ √		x x x			√ √ √		√ √ √		× × ×						
9M	Brecknell Willis HS-P Pan. Horn (Mk2) Low Stress							√√√		√√√	~ ~ ~	x √ √	~ ~ ~	××√	***	***			
	Falverley CX Insulated Pan. Horn																	~ ~ ~	~ ~ ~

Кеу

× = Flashover

✓ = Pass

Failed with both impulse polarities

Passed with one impulse polarity

Passed with both impulse polarities

49



Opportunity – Clearances at Overline Structures

Opportunity – Clearances at Overline Structures

G

00

6

Opportunity – Clearances at Overline Structures





NetworkRail

Other Research & Development

Pilling and pile caps Gradient Uplift & Ice Loading New Feeding Insulated Pantograph **Neutral Sections** Architectures Horns **More Electrical Reducing Bridge** Span Lengths Clearances Parapets

NetworkRail

Pilling and pile caps



09/07/2019

DELE ASSERTER BLEE

Opportunity – Access

- Traditionally construction is through ROTR
- Disadvantages of using ROTR
 - Limited construction time due to setup and handback requirements
 - EGIP 4 hour access time = circa 1 hour construction time
- Opportunity
 - Improved use of EROTR and blockades increased construction efficiency, reduction in many cost drivers
 - Case studies

Shotts project - initially planned primary ROTR, plus EROTR. Project team review, project not able to be delivered in CP5. Agreed access EROTR six nights, plus blockages for critical interventions

EK / Barrhead project – estimated up to 11% saving of project overall cost based upon EROTR and blockades

NetworkRail

Separate rolling programmes

Reduced structure interventions

PASSENG

Focus on reducing project risk in early GRIP Stages

Detailed access (closure) planning